

ERDC/CHL TR-00-3

Coastal and Hydraulics Laboratory



**US Army Corps
of Engineers®**

Engineer Research and
Development Center

First Powerhouse, Bonneville Dam, Columbia River, Oregon Report 2, Tracking Velocities

Hydraulic Model Investigation

Robert Davidson

April 2000

20000505 029

First Powerhouse, Bonneville Dam, Columbia River, Oregon Report 2, Tracking Velocities

Hydraulic Model Investigation

by Robert Davidson

Coastal and Hydraulics Laboratory
U.S. Army Engineer Research and Development Center
3909 Halls Ferry Road
Vicksburg, MS 39180-6199

Report 2 of a series

Approved for public release; distribution is unlimited

Engineer Research and Development Center Cataloging-in-Publication Data

Davidson, Robert A.

First powerhouse, Bonneville Dam, Columbia River, Oregon. Report 2, Tracking velocities , hydraulic model investigation / by Robert Davidson ; prepared for U.S. Army Engineer District, Portland.

63 p. : ill. ; 28 cm. — (ERDC/CHL ; TR-00-3 rept.2)

Includes bibliographic references.

Report 2 of a series.

1. Fishways — Columbia River — Mathematical models. 2. Fish habitat improvement —Columbia River. 3. Fisheries — Oregon. 4. Columbia River. 5. Bonneville Dam (Or. and Wash.) I. United States. Army. Corps of Engineers. Portland District. II. Engineer Research and Development Center (U.S.) III. Coastal and Hydraulics Laboratory (U.S.) IV. Title. V. Series: ERDC/CHL TR ; 00-3 rept.2.
TA7 E8 no.ERDC/CHL TR-00-3 rept.2

Contents

Preface	iv
1—Introduction	1
Background	1
Purpose and Scope	1
2—Scale Model	3
Similitude	3
Interpretation of Experimental Results	4
Model Description	4
Model PSC Description	4
Calibration of Model	5
3—Model Experiments and Results	9
Experimental Conditions	9
1.5240-m (5-ft) slot experiments	9
6.096-m (20-ft) slot experiments	10
4—Conclusions and Recommendations	13
SF 298	

List of Figures

Figure 1. Project location	2
Figure 2. General view of 1:40-scale model	5
Figure 3. Schematic of PSC	6
Figure 4. PSCs in place	7
Figure 5. Gate calibration curves	8
Figure 6. Flow line comparisons	11
Figure 7. Center line flow line comparisons	14

Preface

Velocity experiments to define the flow conditions upstream of prototype surface collector at the First Powerhouse at Bonneville Dam, Columbia River, Portland, OR, were performed for U.S. Army Engineer District, Portland. Funding for this study was received by U.S. Army Engineer Research and Development Center on 14 July 1998.

This study was conducted in the Coastal and Hydraulics Laboratory (CHL), Vicksburg, MS, ERDC, from August 1998 to October 1998 under the direction of Dr. J.R. Houston, Director, CHL, and Dr. P.G. Combs, Chief, Rivers and Structures Division, CHL.

Model velocity information was obtained and plotted by Ms. Danea Polk, hydraulic technician, under the direct supervision of Mr. Robert A. Davidson, research hydraulic engineer. Analysis of the velocity information and final presentation of the information was accomplished by Mr. Davidson under the supervision of Mr. J. F. George, Chief, Fisheries and Structures Hydrodynamic Branch. This report was written by Mr. Davidson.

During the course of the model study, Mr. Randy Lee and Ms. Karen Kuhn, hydraulic engineers, Portland District, visited ERDC to observe model operation, review experiment results, and participate in experiment planning.

At the time of publication of this report the Acting Director of ERDC was Dr. Lewis Link. The Commander was COL Robin R. Cababa, EN.

The contents of this report are not to be used for advertising, publication, or promotional purposes. Citation of trade names does not constitute an official endorsement or approval of the use of such commercial products.

1 Introduction

Background

Bonneville Dam is located on the Columbia River at river mile 146.1, approximately 64.36 km (40 miles) east of Portland, Oregon (Figure 1). It is a multipurpose project that consists of the first and second powerhouses, the old and new navigation locks and a 45,308.8 cu m/sec (1,600,000 cfs)-capacity spillway. Construction of the first powerhouse, the old navigation lock and spillway, began in 1933. President Franklin D. Roosevelt dedicated the lock and dam September 28, 1937. The construction of the first powerhouse was completed in 1943. The first powerhouse has a flow capacity of approximately 3,624.704 cu m/sec (128,000 cfs) and a rated power output of 526,700 kW. Construction of the second powerhouse began in 1974 and was completed in 1981. The second powerhouse has a flow capacity of approximately 4,530.88 cu m/sec (160,000 cfs) and a rated power output of 558,200 kW.

Purpose and Scope

Surface collectors are being studied as a possible solution for bypassing juvenile salmon around the turbines at the Bonneville First Powerhouse. To determine if fish will use the surface collector as a passage route, it is necessary to determine how juvenile salmon will react to the surface collector. Juvenile fish tracking studies were conducted during 1998 in the forebay of the Bonneville First Powerhouse in the area of the prototype surface collector (PSC). Pacific Northwest Laboratories (PNL) acquired the fish movement data. Three-dimensional velocity information was obtained from the 1:40-scale model to overlay with the fish movement data to determine if the juvenile salmon were following the flow lines into the PSC. This velocity information will be delivered to the U.S. Army Engineer District, Portland, who in turn will deliver it to PNL for overlaying with fish movement data.




Figure 1. Project location

2 Scale Model

Similitude

Complete similitude in a laboratory model is attained when geometric, kinematic, and dynamic similitude is satisfied. Physical models of hydraulic structures with both internal flow (pressure flow) and external flow (free surface) typically are scaled using kinematic (Froudian) similitude at a large enough scale that the viscous effects in the scaled model can be neglected. Velocities scaled using kinematic similitude (model Froude number equal to prototype Froude number) in a 1:40-scale model have maximum Reynolds numbers at the peak discharge on the order of 10^5 , yet the corresponding prototype values are on the order of 10^7 .

Because the friction factor decreases with increasing the Reynolds number, the model is hydraulically too rough. The scaled friction losses in the model will be larger than those experienced by the prototype structure. However, the focus of this study is the determination of flow lines in the approach channel and the comparison of the fish movement data to these flow lines. The flow lines are determined through velocity measurements. Only a portion of the powerhouse structure was reproduced so the difference model to prototype friction losses would be difficult to determine. Also, the difference in roughness of the topography between the prototype to the model would be difficult to determine since prototype information on the approach channel is not available. It is very important that the model accurately reproduces enough of the approach topography and specific portions of the intake of the powerhouse to properly develop flow conditions at the powerhouse. The upstream limit of the model was established based on the prototype channel in which the entering flow within the boundaries would be fully developed in the area of consideration. Since the model topography exceeds 20 times the depth upstream from the area being investigated, the velocity measurements in this scale model should compare favorably with those present in the prototype resulting in the determination of accurate flow lines.

Interpretation of Experimental Results

The accepted equations of hydraulic similitude, based on the Froudian relations, were used to express mathematical relations between the dimensions and hydraulic quantities of the model and the prototype. General relations for the transfer of model data to prototype equivalents, or vice versa, are presented in the following tabulation:

Dimension	Ratio	Scale Relations Model:Prototype
Length	$L_r = L$	1:40
Area	$A_r = L_r^2$	1:1600
Velocity	$V_r = L_r^{1/2}$	1:6.32
Time	$T_r = L_r^{1/2}$	1:6.32
Discharge	$Q_r = L_r^{5/2}$	1:10,119

Model Description

A 1:40-scale model of the Bonneville First Powerhouse was constructed in 1995 (Figure 2). All 10-powerhouse units were reproduced from acrylic, including the ice and trash sluiceway and the juvenile bypass channel. Approximately 487.68 m (1,600 ft) of approach topography was also reproduced. The Portland District supplied topographical plots to ERDC, and they were transferred into a digital format. This information was then used to produce templates, which were set to grade in the approach, steel flume that had been fabricated for this model. Concrete was poured and smoothed between the templates. The upstream portions of the new and old navigation locks were reproduced from plastic-coated plywood. In addition, submerged travelling screens and vertical barrier screens were reproduced from brass and installed in the model.

Model PSC Description

Four PSCs (Figure 3) were constructed of plexiglass and installed on the front of Units 3 through 6 (Figure 4). The PSC had a maximum prototype opening of 6.096 m (20 ft), but any opening less than that could be set on the model PSC by the addition of sheet metal coverings. The invert elevation of the PSC floor is at el 30.5 ft. Each individual PSC covers one entire powerhouse turbine unit and the upstream face of the PSC has the same slope as the face of the powerhouse (11.3 deg). Flow will enter the PSC through the front slot and will be passed through the PSC into the three bays of the powerhouse unit of which it is




Figure 2. General view of 1:40-scale model

attached. The sides of the PSC have solid walls that will not allow flow to pass out. This means that any juvenile fish that pass through the PSC will enter the powerhouse unit and will either pass through the turbine or will be guided by the submerged travelling screen. Juvenile fish may pass also through PSC into the ice and trash sluiceway, when the ice and trash sluice gate are open in the turbine unit with the PSC in place. Changing the PSC entrance slot width or changing the turbine discharge will affect the flow through the PSC which in turn has an effect of the ratio of flow through the PSC to flow which passes under the PSC.

Calibration of Model

Water is supplied to the model by six pumps. Each pump is capable of supplying 0.0850 cu m/sec (3 cfs) (model value). This provides a total prototype inflow capacity of approximately 5,153.876 cu m/sec (182,000 cfs). A data industrial flow meter was placed in each inflow supply line. Each flow meter was calibrated in the Coastal and Hydraulic Lab's Volumetric Calibration Flume prior to installation in the supply line.




Figure 3. Schematic of PSC




Figure 4. PSCs in place

Each powerhouse unit was constructed with three vertical control gates located at the center line of the turbine. Each one of the three gates is operated separately and controls flow through an individual bay of the powerhouse unit. Based on information obtained from the 1:25-scale Bonneville First Powerhouse section model, the flow through each bay of the powerhouse unit is nearly equal. The control gates in the powerhouse were calibrated (Figure 5) by setting all gates in the powerhouse to a particular opening. A discharge was set and the upper pool was allowed to settle. This head pool was recorded and then the inflow was increased in the model. This procedure was repeated until the upper pool elevation exceeded elevation¹ (el) 80. This entire procedure was repeated until the flow through each unit exceeded 396.452 cu m/sec (14,000 cfs).

Velocity information was obtained in the model with an Acoustic Doppler Velocity Meter (ADV). Calibration of this instrument was performed by the manufacturer and no additional calibration was required.

¹ All elevation (el) cited herein are in feet referenced to the National Geodetic Vertical Datum (to convert feet to meters, multiply number of feet by 0.3048).




Figure 5. Gate calibration curves

3 Model Experiments and Results

Experimental Conditions

The scope of work that was sent to ERDC by CENWP requested velocity information be obtained in a 2-m by 2-m (prototype) grid around the entrance to the PSC on Unit 3 for both a 1.524 and 6.096-m (5 and 20-ft) slot opening with a floor elevation of 9.2964 m (30.5 ft). The powerhouse discharge settings were as follows: for Units 1, 2, 7, 8, 9, and 10, discharges were set at 319.9934 cu m/sec (11,300 cfs); Units 3 and 5 discharges were set at 277.5164 cu m/sec (9,800 cfs); Units 4 and 6 were off. The forebay elevation was 74.5. Sluiceway 10C was open to el 71.5, sluiceway 5B was open to el 71.8, sluiceway 3B was open to el 72.0 and sluiceway 7A was open to el 73.9. These were the average prototype First Powerhouse conditions during the fish tracking experiments in 1998.

1.5240-m (5-ft) slot experiments

The model was set up according to the outlined experimental conditions. Two strips of sheet metal were added to the front of the PSC to reduce the slot entrance width from 6.096 m to 1.5240 m (20 ft to 5 ft). Velocities were obtained at a depth of 0.2926 m (0.96 ft) along the center line of the PSC and upstream of the PSC in 1.9995-m (6.56-ft) increments to a distance of 16.1331 m (52.93 ft). Velocities were also obtained at 1.9995, 3.999, 5.9985, and 8.001 m (6.56, 13.12, 19.68, and 26.25 ft) to the left and right (looking downstream) of each velocity measurement along the center line. This grid was repeated for depths of 1.9995, 3.999, 5.9985, 8.001, 9.9974, 12.0, 13.9995, 15.999, 17.9984, 19.9813, 22.0005, and 23.0002 m (6.56, 13.12, 19.68, 26.25, 32.8, 39.37, 45.93, 52.49, 59.05, 65.62, 72.18, and 75.46 ft). Measured velocities showed a fairly equal velocity distribution of 16.6036 m (54.49 ft) upstream of the PSC (Plates 1-9). However, the closer the velocity was measured to the PSC (except for along the center line) the higher the velocity magnitude was below the collector than above the floor of the collector. This shows the blockage of flow to the turbine caused by the PSC which results in a steeper downward flow component above the collector floor. Velocity measured along the center line

showed a closer velocity magnitude and direction relationship between flow below the PSC floor and flow above the PSC floor (Plate 1). This indicates that if juvenile fish followed flow lines they might enter the PSC if they happen to be in the flow lines that supply water to the PSC. The velocities recorded in Plates 1- 9 reflect only the vertical and perpendicular velocity components. Plan view plots (lateral and perpendicular velocity components) indicate that fish that are to the right (looking downstream) of the PSC entrance flow line may be directed to the PSC (Plates 10-22). The negative side of the flow area to the right (and left) of the center line is that this is in an area where the vertical component of the velocity becomes more negative (downward) the closer it approaches the PSC (Figure 6). Only biological fish tracking experiments performed at the prototype structure with the PSC in place will determine if the conditions described by these velocity experiments are conducive to effective fish collection.

6.096-m (20-ft) slot experiments

The model was set up according to the outlined experimental conditions. The slot opening on the front of the PSC was 6.096 m (20 ft). Velocities were obtained at a depth of 0.2926 m (0.96 ft) along the center line of the PSC and upstream of the PSC in 1.9995-m (6.56-ft) increments to a distance of 16.1331 m (52.93 ft). Velocities were also obtained at 1.9995, 3.999, 5.9985, and 8.001 m (6.56, 13.12, 19.68, and 26.25 ft) to the left and right, looking downstream, of each velocity measurement along the center line. This grid was repeated for depths of 1.9995, 3.999, 5.9985, 8.001, 9.9974, 12.0, 13.9995, 15.999, 17.9984, 19.9813, 22.0005, and 23.0002 m (6.56, 13.12, 19.68, 26.25, 32.8, 39.37, 45.93, 52.49, 59.05, 65.62, 72.18, and 75.46 ft). Measured velocities showed a fairly equal velocity distribution 15.999 m (52.49 ft) upstream of the PSC (Plates 23-31). However, the closer the velocity was measured to the PSC (except for along the center line and 1.9995 m (6.56 ft) to the left and right of center line) the higher the velocity was below the collector floor than above the floor. This shows the blockage of flow to the turbine that the PSC causes. Velocity measured along the center line and 1.9995 m (6.56 ft) to the left and right of center line showed a higher velocity, at the face of the PSC, above the floor of the PSC than velocities below the PSC floor. This is true at the PSC face, but the velocities upstream showed a more comparable top to bottom velocity magnitude. This indicates that if juvenile fish followed the flow lines they might enter the PSC if they happen to be in the flow lines that supply water to the PSC. The velocities recorded in Plates 23-31 reflect only the vertical and perpendicular velocity components. Plan view plots (lateral and perpendicular velocity components) indicate that fish that are to the right (looking downstream) of the PSC entrance flow line may be directed to the PSC (Plates 34-44). The negative side of the flow area to the right (and left) of the center line is that this is in an area where the vertical component of the velocity becomes more negative (downward) the closer it approaches the PSC. This was not as dramatic as the vertical velocities components obtained with the 1.524-m (5-ft) slot




Figure 6. Flow line comparisons

opening, but it still occurs with the 6.096-m (20-ft) slot opening. Only biological experiments performed at the prototype structure with the PSC in place, with a 6.096-m (20-ft) opening, will determine if the conditions described by these velocity experiments are conducive to effective fish collection.

4 Conclusions and Recommendations

The 6.096-m (20-ft) PSC slot opening velocity profiles indicated a higher potential for capturing a greater number of fish than the 1.524-m (5-ft) if fish follow flow lines (Figure 7). This is because the 6.096-m (20-ft) slot opening reduces the blockage effect of the PSC by allowing more turbine flow to pass through the PSC. The velocity profiles showed a negative (downward) vertical velocity component the closer the flow was to the PSC face for both a 1.524-m (5-ft) and 6.096-m (20-ft) opening. Field results of fish tracks, with comparable powerhouse conditions, should be compared to these approach flow conditions in order to truly assess the effectiveness of the PSC on intercepting juvenile salmon. This will be done by PNL.

Also, since the flow of the turbine greatly affects the flow through the PSC, fish tracking information should be obtained for several different turbine loadings for both the 1.524-m (5-ft) and 6.096-m (20-ft) PSC openings. Velocity information should be obtained for each of these conditions and these should be compared to the fish track information. This is necessary to insure enough fish behavior and hydraulic information is available to design a permanent surface collector for this project.







Figure 7. Center line flow line comparisons









UNIT1: 11.3kcs UNIT6: OFF
 UNIT2: 11.3kcs UNIT7: 11.3kcs
 UNIT3: 98kcs UNIT8: 11.3kcs
 UNIT4: OFF UNIT9: 11.3kcs
 UNIT5: 98kcs UNIT10: 11.3kcs
 1998 PSC ON UNITS 3, 4, 5, AND 6 AT EL. 30.5'
 5' SLOT OPENING ON PSC
 VELOCITIES OBTAINED 2 METERS RIGHT OF CENTERLINE OF UNIT 3
 LOOKING DOWNSTREAM
 POOL ELEVATION 74.5'

PSC98EL.DVG
 JULY 1998
 VELOCITIES ARE PLOTTED IN FEET PER SECOND
 VELOCITIES SHOWN ARE A COMBINATION RESULTANT OF VERTICAL AND PERPENDICULAR COMPONENTS
 VELOCITY POSITION IS AT TAIL OF VECTOR


Plate 4








VELOCITIES ARE PLOTTED IN FEET PER SECOND
VELOCITIES SHOWN ARE A COMBINATION RESULT
VELOCITY POSITION IS AT TAIL OF VECTOR


SCOT OPENING ON FSC
4 METERS RIGHT OF CENTERLINE OF UNIT 3
LOOKING DOWNSTREAM
POOL ELEVATION 74.5'













UNIT 3




COLLECTORS ON UNITS 3,4,5, AND 6
PSC AT EL 30.5 POOL AT EL 74.5
5' SLOT OPENING ON PSC
UNIT1: 11.3 UNIT 6: OFF
UNIT2: 11.3 UNIT7: 11.3
UNIT3: 9.8 UNIT8: 11.3
UNIT4: OFF UNIT9: 11.3
UNIT5: 9.8 UNIT10: 11.3
VELOCITIES 2 METERS BELOW WATER SURFACE

PSC98PL.DWG
PSC TEST 1998
VELOCITIES ARE PLOTTED IN FEET PER SECOND
VELOCITIES SHOWN ARE A COMBINATION RESULTANT OF LATERAL AND PERPENDICULAR COMPONENTS
VELOCITY POSITION IS AT TAIL OF VECTOR




UNIT 3




PSC

17	15	14	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100	101	102	103	104	105	106	107	108	109	110	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500	501	502	503	504	505	506	507	508	509	510	511	512	513	514	515	516	517	518	519	520	521	522	523	524	525	526	527	528	529	530	531	532	533	534	535	536	537	538	539	540	541	542	543	544	545	546	547	548	549	550	551	552	553	554	555	556	557	558	559	560	561	562	563	564	565	566	567	568	569	570	571	572	573	574	575	576	577	578	579	580	581	582	583	584	585	586	587	588	589	590	591	592	593	594	595	596	597	598	599	600	601	602	603	604	605	606	607	608	609	610	611	612	613	614	615	616	617	618	619	620	621	622	623	624	625	626	627	628	629	630	631	632	633	634	635	636	637	638	639	640	641	642	643	644	645	646	647	648	649	650	651	652	653	654	655	656	657	658	659	660	661	662	663	664	665	666	667	668	669	670	671	672	673	674	675	676	677	678	679	680	681	682	683	684	685	686	687	688	689	690	691	692	693	694	695	696	697	698	699	700	701	702	703	704	705	706	707	708	709	710	711	712	713	714	715	716	717	718	719	720	721	722	723	724	725	726	727	728	729	730	731	732	733	734	735	736	737	738	739	740	741	742	743	744	745	746	747	748	749	750	751	752	753	754	755	756	757	758	759	760	761	762	763	764	765	766	767	768	769	770	771	772	773	774	775	776	777	778	779	780	781	782	783	784	785	786	787	788	789	790	791	792	793	794	795	796	797	798	799	800	801	802	803	804	805	806	807	808	809	810	811	812	813	814	815	816	817	818	819	820	821	822	823	824	825	826	827	828	829	830	831	832	833	834	835	836	837	838	839	840	841	842	843	844	845	846	847	848	849	850	851	852	853	854	855	856	857	858	859	860	861	862	863	864	865	866	867	868	869	870	871	872	873	874	875	876	877	878	879	880	881	882	883	884	885	886	887	888	889	890	891	892	893	894	895	896	897	898	899	900	901	902	903	904	905	906	907	908	909	910	911	912	913	914	915	916	917	918	919	920	921	922	923	924	925	926	927	928	929	930	931	932	933	934	935	936	937	938	939	940	941	942	943	944	945	946	947	948	949	950	951	952	953	954	955	956	957	958	959	960	961	962	963	964	965	966	967	968	969	970	971	972	973	974	975	976	977	978	979	980	981	982	983	984	985	986	987	988	989	990	991	992	993	994	995	996	997	998	999	1000	1001	1002	1003	1004	1005	1006	1007	1008	1009	1010	1011	1012	1013	1014	1015	1016	1017	1018	1019	1020	1021	1022	1023	1024	1025	1026	1027	1028	1029	1030	1031	1032	1033	1034	1035	1036	1037	1038	1039	1040	1041	1042	1043	1044	1045	1046	1047	1048	1049	1050	1051	1052	1053	1054	1055	1056	1057	1058	1059	1060	1061	1062	1063	1064	1065	1066	1067	1068	1069	1070	1071	1072	1073	1074	1075	1076	1077	1078	1079	1080	1081	1082	1083	1084	1085	1086	1087	1088	1089	1090	1091	1092	1093	1094	1095	1096	1097	1098	1099	1100	1101	1102	1103	1104	1105	1106	1107	1108	1109	1110	1111	1112	1113	1114	1115	1116	1117	1118	1119	1120	1121	1122	1123	1124	1125	1126	1127	1128	1129	1130	1131	1132	1133	1134	1135	1136	1137	1138	1139	1140	1141	1142	1143	1144	1145	1146	1147	1148	1149	1150	1151	1152	1153	1154	1155	1156	1157	1158	1159	1160	1161	1162	1163	1164	1165	1166	1167	1168	1169	1170	1171	1172	1173	1174	1175	1176	1177	1178	1179	1180	1181	1182	1183	1184	1185	1186	1187	1188	1189	1190	1191	1192	1193	1194	1195	1196	1197	1198	1199	1200	1201	1202	1203	1204	1205	1206	1207	1208	1209	1210	1211	1212	1213	1214	1215	1216	1217	1218	1219	1220	1221	1222	1223	1224	1225	1226	1227	1228	1229	1230	1231	1232	1233	1234	1235	1236	1237	1238	1239	1240	1241	1242	1243	1244	1245	1246	1247	1248	1249	1250	1251	1252	1253	1254	1255	1256	1257	1258	1259	1260	1261	1262	1263	1264	1265	1266	1267	1268	1269	1270	1271	1272	1273	1274	1275	1276	1277	1278	1279	1280	1281	1282	1283	1284	1285	1286	1287	1288	1289	1290	1291	1292	1293	1294	1295	1296	1297	1298	1299	1300	1301	1302	1303	1304	1305	1306	1307	1308	1309	1310	1311	1312	1313	1314	1315	1316	1317	1318	1319	1320	1321	1322	1323	1324	1325	1326	1327	1328	1329	1330	1331	1332	1333	1334	1335	1336	1337	1338	1339	1340	1341	1342	1343	1344	1345	1346	1347	1348	1349	1350	1351	1352	1353	1354	1355	1356	1357	1358	1359	1360	1361	1362	1363	1364	1365	1366	1367	1368	1369	1370	1371	1372	1373	1374	1375	1376	1377	1378	1379	1380	1381	1382	1383	1384	1385	1386	1387	1388	1389	1390	1391	1392	1393	1394	1395	1396	1397	1398	1399	1400	1401	1402	1403	1404	1405	1406	1407	1408	1409	1410	1411	1412	1413	1414	1415	1416	1417	1418	1419	1420	1421	1422	1423	1424	1425	1426	1427	1428	1429	1430	1431	1432	1433	1434	1435	1436	1437	1438	1439	1440	1441	1442	1443	1444	1445	1446	1447	1448	1449	1450	1451	1452	1453	1454	1455	1456	1457	1458	1459	1460	1461	1462	1463	1464	1465	1466	1467	1468	1469	1470	1471	1472	1473	1474	1475	1476	1477	1478	1479	1480	1481	1482	1483	1484	1
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	---




UNIT 3



1.6	1.4	1.0	0.7	3.2	2.1	1.9	1.6	1.5
1.4	1.2	1.1	1.1	1.7	1.7	1.4	1.2	1.1
1.5	1.5	1.5	1.4	1.5	1.5	1.4	1.4	1.3
1.3	1.6	1.5	1.5	1.7	1.4	1.4	1.3	1.3
1.7	1.5	1.7	1.5	1.5	1.5	1.5	1.5	1.4
1.6	1.6	1.6	1.7	1.7	1.4	1.5	1.5	1.4
1.6	1.5	1.7	1.5	1.7	1.5	1.5	1.4	1.4
1.5	1.4	1.6	1.4	1.7	1.4	1.5	1.3	1.3

COLLECTORS ON UNITS 3,4,5, AND 6
PSC AT EL 30.5 POOL AT EL 74.5
5' SLOT OPENING ON PSC
UNIT1: 11.3 UNIT 6: OFF
UNIT2: 11.3 UNIT7: 11.3
UNIT3: 9.8 UNIT8: 11.3
UNIT4: OFF UNIT9: 11.3
UNIT5: 9.8 UNIT10: 11.3
VELOCITIES 10 METERS BELOW WATER SURFACE

PSC98PL.DWG
PSC TEST 1998
VELOCITIES ARE PLOTTED IN FEET PER SECOND
VELOCITIES SHOWN ARE A COMBINATION RESULTANT OF LATERAL AND PERPENDICULAR COMPONENTS
VELOCITY POSITION IS AT TAIL OF VECTOR

[illegible]


COLLECTORS ON UNITS 3,4,5, AND 6
PSC AT EL 30.5 POOL AT EL 74.5

5' SLOT	OPENING ON	PSC
UNIT1:	UNIT 6:	OFF
UNIT1:	UNIT7:	11.3
UNIT2:	UNIT8:	11.3
UNIT3:	UNIT9:	11.3
UNIT4:	UNIT10:	11.3
UNIT5:		11.3

VELOCITIES 12 METERS BELOW WATER SURFACE

PSC98PL.DWG
PSC TEST 1998
VELOCITIES ARE
VELOCITIES SHD
VELOCITY POSIT

UNIT 3



2.3	2.2	1.8	3.7	3.0	2.6	2.0	3.1	3.1
1.7	1.9	1.8	2.0	2.1	1.9	1.8	1.9	2.0
1.8	1.7	1.8	1.8	1.9	1.8	1.8	1.7	1.7
1.8	1.7	1.8	1.7	1.8	1.7	1.6	1.7	1.6
1.7	1.5	1.7	1.5	1.7	1.6	1.7	1.4	1.6
1.6	1.5	1.5	1.7	1.7	1.6	1.6	1.5	1.5
1.3	1.5	1.5	1.6	1.6	1.5	1.4	1.5	1.4
1.5	1.6	1.7	1.3	1.8	1.6	1.5	1.5	1.4

COLLECTORS ON UNITS 3,4,5, AND 6
PSC AT EL 30.5 POOL AT EL 74.5

5' SLOT OPENING ON PSC
UNIT1: 11.3 UNIT 6: OFF
UNIT2: 11.3 UNIT7: 11.3
UNIT3: 9.8 UNIT8: 11.3
UNIT4: OFF UNIT9: 11.3
UNIT5: 9.8 UNIT10: 11.3

VELOCITIES 14 METERS BELOW WATER SURFACE


PSC98PL.DWG

PSC TEST 1998


VELOCITIES ARE PLOTTED IN FEET PER SECOND

VELOCITIES SHOWN ARE A COMBINATION RESULTANT OF LATERAL AND PERPENDICULAR COMPONENTS

VELOCITY POSITION IS AT TAIL OF VECTOR



UNIT 3



25	25	26	26	27	27	28	28
23	24	24	25	27	24	24	25
21	21	22	22	23	22	22	21
19	19	19	20	22	19	18	19
17	18	18	18	20	17	17	16
15	16	17	16	18	16	17	16
16	16	16	16	17	16	16	14
17	17	15	16	16	15	15	16
							13

COLLECTORS ON UNITS 3,4,5, AND 6
PSC AT EL 30.5 POOL AT EL 74.5

5' SLOT OPENING ON PSC
UNIT1: 11.3 UNIT 6: OFF

UNIT2: 11.3 UNIT7: 11.3


UNIT3: 9.8 UNIT8: 11.3

UNIT4: OFF UNIT9: 11.3


UNIT5: 9.8 UNIT10: 11.3

VELOCITIES 18 METERS BELOW WATER SURFACE

PSC98PLDWG
PSC TEST 1998
VELOCITIES ARE PLOTTED IN FEET PER SECOND
VELOCITIES SHOWN ARE A COMBINATION RESULTANT OF LATERAL AND PERPENDICULAR COMPONENTS
VELOCITY POSITION IS AT TAIL OF VECTOR



UNIT 3



24	26	27	26	26	26	26	27	26	26	25	24
24	23	25	26	26	26	26	26	26	26	25	24
22	22	23	22	22	22	23	21	22	22	22	20
20	20	21	20	21	21	21	19	20	20	17	17
19	18	20	18	18	18	18	18	15	15	16	16
17	03	18	16	17	18	16	16	15	15	15	15
14	17	17	16	16	15	15	15	15	15	14	14
14	13	15	15	15	15	15	14	14	14	14	12

COLLECTORS ON UNITS 3,4,5, AND 6
PSC AT EL 30.5 POOL AT EL 74.5

5' SLOT OPENING ON PSC
UNIT1: 11.3 UNIT 6: OFF
UNIT2: 11.3 UNIT7: 11.3
UNIT3: 9.8 UNIT8: 11.3
UNIT4: OFF UNIT9: 11.3
UNIT5: 9.8 UNIT10: 11.3

VELOCITIES 22 METERS BELOW WATER SURFACE


PSC98PL.DWG


PSC TEST 1998

VELOCITIES ARE PLOTTED IN FEET PER SECOND

VELOCITIES SHOWN ARE A COMBINATION RESULTANT OF LATERAL AND PERPENDICULAR COMPONENTS


VELOCITY POSITION IS AT TAIL OF VECTOR







UNIT1: 11.3kcfs UNIT6: OFF
 UNIT2: 11.3kcfs UNIT7: 11.3kcfs
 UNIT3: 9.8kcfs UNIT8: 11.3kcfs
 UNIT4: OFF UNIT9: 11.3kcfs
 UNIT5: 9.8kcfs UNIT10: 11.3kcfs
 1998 PSC ON UNITS 3, 4, 5, AND 6 AT EL. 30.5'
 20' SLOT OPENING ON PSC
 VELOCITIES OBTAINED ALONG CENTERLINE OF UNIT 3
 LOOKING DOWNSTREAM
 POOL ELEVATION 74.5'


PSC98ELJWG
 JULY 1998
 VELOCITIES ARE PLOTTED IN FEET PER SECOND
 VELOCITIES SHOWN ARE A COMBINATION RESULTANT OF VERTICAL AND PERPENDICULAR COMPONENTS
 VELOCITY POSITION IS AT TAIL OF VECTOR











PSC98L.DWG
JULY 1998
VELOCITIES ARE PLOTTED IN FEET PER SECOND
VELOCITIES SHOWN ARE A COMBINATION RESULTANT OF VERTICAL AND PERPENDICULAR COMPONENTS
VELOCITY POSITION IS AT TAIL OF VECTOR













UNIT 3




COLLECTORS ON UNITS 3,4,5, AND 6
PSC AT EL 30.5 POOL AT EL 74.5
20' SLOT OPENING ON PSC
UNIT1: 11.3 UNIT 6: OFF
UNIT2: 11.3 UNIT7: 11.3
UNIT3: 9.8 UNIT8: 11.3
UNIT4: OFF UNIT9: 11.3
UNIT5: 9.8 UNIT10: 11.3

VELOCITIES 2 METERS BELOW WATER SURFACE

PSC98PL.DWG
PSC TEST 1998
VELOCITIES ARE PLOTTED IN FEET PER SECOND
VELOCITIES SHOWN ARE A COMBINATION RESULTANT OF LATERAL AND PERPENDICULAR COMPONENTS
VELOCITY POSITION IS AT TAIL OF VECTOR



UNIT 3



12	0.7	1.2	2.5	3.6	4.2	5.1	6.3	1.9
12	0.8	0.8	2.0	3.1	3.4	2.9	2.3	1.9
11	0.8	1.0	1.4	2.3	2.1	2.0	1.7	1.4
14	1.2	1.3	1.5	1.9	1.8	1.8	1.7	1.5
14	1.3	1.3	1.5	1.8	1.6	1.6	1.4	1.4
16	1.6	1.4	1.7	1.7	1.6	1.7	1.7	1.5
14	1.5	1.5	1.6	1.7	1.5	1.6	1.4	1.4
16	1.6	1.7	1.6	1.7	1.7	1.6	1.6	1.3
15	1.5	1.5	1.7	1.7	1.5	1.4	1.4	1.5

COLLECTORS ON UNITS 3,4,5, AND 6
PSC AT EL 30.5 POOL AT EL 74.5

20' OPENING ON PSC
UNIT1: 11.3 UNIT 6: OFF

UNIT2: 11.3 UNIT7: 11.3

UNIT3: 9.8 UNIT8: 11.3

UNIT4: OFF UNIT9: 11.3

UNIT5: 9.8 UNIT10: 11.3

VELOCITIES 6 METERS BELOW WATER SURFACE


PSC98PL.DWG

PSC TEST 1998

VELOCITIES ARE PLOTTED IN FEET PER SECOND

VELOCITIES SHOWN ARE A COMBINATION RESULTANT OF LATERAL AND PERPENDICULAR COMPONENTS

VELOCITY POSITION IS AT TAIL OF VECTOR



CS
S
P

COLLECTORS ON UNITS 3,4,5, AND 6
PSC AT EL 30.5 POOL AT EL 74.5

20' SLOT OPENING ON PSC

UNIT1: 11.3 UNIT 6: OFF

UNIT 1:	UNIT 5:	UNIT 9:
UNIT 2:	UNIT 6:	UNIT 10:
UNIT 3:	UNIT 7:	UNIT 11:
UNIT 4:	UNIT 8:	UNIT 12:

UNIT 2:	11.3	UNIT 7:	11.3
UNIT 3:	9.8	UNIT 8:	11.3

UNIT 3:	9.8	UNIT 8:	11.3
UNIT 4:	OFF	UNIT 9:	11.3

UNIT4:	OFF	UNIT9:	11.3
UNIT5:	9.8	UNIT10:	11.3


UNIT 15: 9.8 UNIT 10: 11.3
VELOCITIES 8 METERS BELOW WATER SURFACE

PSC98PL.DWG
PSC TEST 1998

VELOCITIES ARE PLOTTED IN FEET PER SECOND

VELOCITIES SHOWN ARE A COMBINATION RESULTANT OF LATERAL AND PERPENDICULAR COMPONENTS
VELOCITY POSITION IS AT TAIL OF VECTOR

UNIT 3




1.1	0.8	0.6	2.2	3.4	4.0	3.2	2.2	1.8
1.3	1.0	1.0	1.4	2.5	2.3	2.2	1.9	1.5
1.3	1.1	1.4	1.6	2.1	2.0	1.9	1.7	1.5
1.4	1.4	1.6	1.6	1.8	1.8	1.8	1.6	1.6
1.6	1.5	1.5	1.6	1.8	1.8	1.7	1.6	1.4
1.6	1.6	1.7	1.6	1.7	1.7	1.6	1.6	1.5
1.6	1.6	1.5	1.6	1.7	1.6	1.5	1.6	1.5
1.6	1.5	1.6	1.5	1.7	1.7	1.6	1.4	1.5

COLLECTORS ON UNITS 3,4,5, AND 6
PSC AT EL 30.5 POOL AT EL 74.5


20' SLOT OPENING ON PSC
UNIT1: 11.3 UNIT 6: OFF
UNIT2: 11.3 UNIT7: 11.3
UNIT3: 9.8 UNIT8: 11.3
UNIT4: OFF UNIT9: 11.3
UNIT5: 9.8 UNIT10: 11.3

VELOCITIES 10 METERS BELOW WATER SURFACE

PSC98PL.DWG
PSC TEST 1998
VELOCITIES ARE PLOTTED IN FEET PER SECOND
VELOCITIES SHOWN ARE A COMBINATION RESULTANT OF LATERAL AND PERPENDICULAR COMPONENTS
VELOCITY POSITION IS AT TAIL OF VECTOR



UNIT 3



2.0	2.6	2.4	2.8	2.7	2.5	2.5	2.7
1.7	1.7	2.0	2.3	2.1	1.9	1.9	1.7
1.6	1.5	1.6	1.7	2.1	1.9	1.8	1.8
1.7	1.7	1.6	1.7	2.0	1.9	1.8	1.5
1.7	1.6	1.6	1.6	1.8	1.6	1.6	1.7
1.5	1.5	1.6	1.7	1.6	1.5	1.7	1.5
1.5	1.5	1.5	1.8	1.6	1.6	1.6	1.5
1.5	1.5	1.6	1.5	1.7	1.4	1.5	1.4
							1.3

COLLECTORS ON UNITS 3,4,5, AND 6
PSC AT EL 30.5 POOL AT EL 74.5

20' SLOT OPENING ON PSC
UNIT1: 11.3 UNIT 6: OFF
UNIT2: 11.3 UNIT7: 11.3
UNIT3: 9.8 UNIT8: 11.3
UNIT4: OFF UNIT9: 11.3
UNIT5: 9.8 UNIT10: 11.3

VELOCITIES 14 METERS BELOW WATER SURFACE


PSC98PL.DWG

PSC TEST 1998


VELOCITIES ARE PLOTTED IN FEET PER SECOND

VELOCITIES SHOWN ARE A COMBINATION RESULTANT OF LATERAL AND PERPENDICULAR COMPONENTS

VELOCITY POSITION IS AT TAIL OF VECTOR




UNIT 3




20	21	21	24	22	24	23
20	20	19	21	21	21	21
20	18	19	19	20	20	18
17	18	17	19	17	17	18
17	17	17	16	18	16	16
16	14	16	16	18	16	16
16	16	15	15	17	15	15
15	16	16	15	16	15	15

COLLECTORS ON UNITS 3,4,5, AND 6
PSC AT EL 30.5 POOL AT EL 74.5
20' SLOT OPENING ON PSC
UNIT1: 11.3 UNIT 6: OFF
UNIT2: 11.3 UNIT7: 11.3
UNIT3: 9.8 UNIT8: 11.3
UNIT4: OFF UNIT9: 11.3
UNIT5: 9.8 UNIT10: 11.3
VELOCITIES 18 METERS BELOW WATER SURFACE

PSC98PL.DWG
PSC TEST 1998
VELOCITIES ARE PLOTTED IN FEET PER SECOND
VELOCITIES SHOWN ARE A COMBINATION RESULTANT OF LATERAL AND PERPENDICULAR COMPONENTS
VELOCITY POSITION IS AT TAIL OF VECTOR





PS

22	21	22	21	20	21	22	21	20	21	22	21	20
20	21	20	21	20	21	20	21	20	21	20	21	20
19	19	20	19	19	19	19	19	19	19	18	18	18
17	17	18	17	17	16	17	16	17	17	16	16	16
17	18	17	16	16	16	15	16	15	16	14	15	15
17	03	16	16	15	15	15	13	14	13	13	13	13
15	03	16	16	15	15	15	13	15	13	13	13	13
13	14	03	14	15	13	13	15	13	13	13	13	13

COLLECTORS ON UNITS 3,4,5, AND 6
PSC AT EL 30.5 POOL AT EL 74.5

UNIT	20' SLOT	OPENING	IN	PSC
UNIT1:	11.3	UNIT 6:		OFF
UNIT2:	11.3	UNIT7:		11.3
UNIT3:	9.8	UNIT8:		11.3
UNIT4:	9.8	UNIT9:		11.3
UNIT5:	9.8	UNIT10:		11.3

VELOCITIES 22 METERS BELOW WATER SURFACE

PSC98PL.DWG
PSC TEST 1998

FSC TEST 1978
VELOCITIES ARE PLOTTED IN FEET PER SECOND
VELOCITIES SHOWN ARE A COMBINATION RESULTS
VELOCITY POSITION IS AT TAIL OF VECTOR



REPORT DOCUMENTATION PAGE*Form Approved*
OMB No. 0704-0188

Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing this collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden to Department of Defense, Washington Headquarters Services, Directorate for Information Operations and Reports (0704-0188), 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number. **PLEASE DO NOT RETURN YOUR FORM TO THE ABOVE ADDRESS.**

1. REPORT DATE (DD-MM-YYYY)

April 2000

2. REPORT TYPE

Final report

3. DATES COVERED (From - To)**4. TITLE AND SUBTITLE**

First Powerhouse, Bonneville Dam, Columbia River, Oregon, Report 2, Tracking Velocities; Hydraulic Model Investigation

5a. CONTRACT NUMBER**5b. GRANT NUMBER****5c. PROGRAM ELEMENT NUMBER****6. AUTHOR(S)**

Robert Davidson

5d. PROJECT NUMBER**5e. TASK NUMBER****5f. WORK UNIT NUMBER****7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES)**U.S. Army Engineer Research and Development Center
Coastal and Hydraulics Laboratory
3909 Halls Ferry Road
Vicksburg, MS 39180-6199**8. PERFORMING ORGANIZATION REPORT NUMBER**

ERDC/CHL TR-00-3

9. SPONSORING / MONITORING AGENCY NAME(S) AND ADDRESS(ES)U.S. Army Engineer District, Portland
P.O. Box 2946
Portland, OR 97208-2946**10. SPONSOR/MONITOR'S ACRONYM(S)****11. SPONSOR/MONITOR'S REPORT NUMBER(S)****12. DISTRIBUTION / AVAILABILITY STATEMENT**

Approved for public release; distribution is unlimited.

13. SUPPLEMENTARY NOTES**14. ABSTRACT**

Surface collectors are being studied as a possible solution for bypassing juvenile salmon around the turbines. Juvenile fish tracking studies were conducted in 1998 in the forebay of the powerhouse in the vicinity of the surface collector. A 1:40-scale model of the powerhouse was utilized to obtain three-dimensional velocity information in the same vicinity of the surface collector. The velocity information was provided to Portland District to overlay with the fish tracking data to determine if the juvenile salmon were following the flow lines into the surface collector.

15. SUBJECT TERMS

Fish Bypass Structure, Powerhouse, Surface collectors

16. SECURITY CLASSIFICATION OF:**a. REPORT**

UNCLASSIFIED

b. ABSTRACT

UNCLASSIFIED

c. THIS PAGE

UNCLASSIFIED

17. LIMITATION OF ABSTRACT**18. NUMBER OF PAGES**

63

19a. NAME OF RESPONSIBLE PERSON**19b. TELEPHONE NUMBER (include area code)**